

Our Capabilities



Contract

Mount Barker Bypass Road

Client

Main Roads Western Australia

Consultant

Contract Value

\$8,026,000

Contract Start Date

March 2007

Contract Completion Date

July 2008

Description

The contract involved the construction of 4.7km of single lane carriageway bypassing the town centre of Mount Barker with associated intersections, slip lanes, a major roundabout on Albany Highway and extensive traffic management.

Ertech's scope of work included:

- 111,000m³ earthworks
- 101,000m² subgrade
- 90,000m² of 140mm thick subbase
- 76,000m² of 210mm thick basecourse
- 62,000m² of 10mm single coat seal
- 29,000m² of 40mm asphalt
- 1,020m of piped drainage (300mm to 750mØ) with insitu headwalls
- Kerbing
- Linemarking
- Signage

For further details about this project or any of our services, please contact:
Ertech Pty Ltd on (08) 9302 6666 or
ertech@ertech.com.au