

Olympic Dam Evaporation Pond 5

Project

Olympic Dam Evaporation Pond 5

Client/EPCM

BHP Billiton

Value

\$11,564,932

Description

The construction of Olympic Dam's Evaporation Pond 5 involved the following:

- 32 hectares clearing and topsoil stripping
- 40,000m³ cut to fill
- 420,000m³ borrow to fill
- 180,000m³ cut to spoil
- 250,000m² of clay and 1.5mm HDPE lining
- 2 access platform structures
- 2,500m of HDPE liquor pipelines
- 2 pig launching stations
- 2 pig launching receiving stations
- 50,000m² pavement construction
- Installation of 4 safety showers
- 2,600m security fence

Location

Olympic Dam is located at Roxby Downs, 560km north of Adelaide, South Australia.



"...getting it right and on time"