

Tamala Park Landfill Stage 2A & 2B

Construction - Greenfields Infrastructure

Project

Tamala Park Landfill Stage 2A and 2B North

Client/EPCM

Mindarie Regional Council / Sinclair Knight Merz

Value

\$7,185,844

Description

Tamala Park is the main refuse site for the northern suburbs in Perth. Ertech completed the bulk excavation which also included roadworks and HDPE lining.

Ertech's contract included the following works:

- 1,600,000m³ bulk excavation including 50,000m³ of hard rock
- 17,000m² of 1.5mm thick HDPE liner including filter/aggregate layers totaling 1.1m thick
- 314,000m² pavement
- 1.5km pipework and specialist leachate pump including concrete structures
- Excavated sand material was screened on site to provide some of the protective layers for the HDPE liner

Location

Tamala Park is located in the northern suburbs of the Perth metropolitan area, Western Australia.



"...getting it right and on time"