

MSB Upgrade Onshore Works Package B1

Construction - Marine Works

Project

Mermaid Supply Base Upgrade 2008
Onshore Works - Package B1

Client/EPCM

Mermaid Marine Australia Limited

Value

\$13,950,000

Description

Construction of 50,000m² of marine load out pavement areas and associated services and pipework including rock armour walls:

- 100,000m³ earthworks
- 50,000m² subgrade
- 50,000m³ 375mm roadbase
- 50,000m² prime and seal
- 50,000m² 50mm PMB asphalt
- 3000m³ of In-situ concrete works
- Piped drainage - 5,000m of varying size (100mm-750mm) with in-situ concrete headwalls
- Kerbing
- Line marking
- Signage
- Installation of services for 30 site offices and buildings

Location

Dampier is located approximately 1562km north of Perth, Western Australia.



"...getting it right and on time"